PLUMBING FIXTURE SCHEDULE

MARK	DESCRIPTION	FIXTURE CONNECTIONS					MOUNTING HEIGHT	FLOW RATE	MANUFACTURER AND MODEL NUMBER				
		HOT WATER	COLD WATER	WASTE	VENT	OTHER			FIXTURE	FAUCET/FLUSH VALVE	ACCESSORY #1	ACCESSORY #2	REMARKS
EWC-1	ELECTRIC WATER COOLER, DOUBLE BUBBLER, WITH...	---	1/2"	1-1/2"	1-1/2"	---	SEE ARCHITECTURAL	8 GPH					
FCO	FLOOR CLEANOUT	---	---	SEE PLANS	---	---	FLOOR MOUNT	---					
FD-1	FLOOR DRAIN (SQUARE TOP)	---	---	SEE PLANS	SEE PLANS	---	FLOOR MOUNT	---					
L-1	LAVATORY, WALL HUNG, ADA	1/2"	1/2"	1 1/4"	1 1/4"	---	WALL HUNG, SEE ARCHITECTURAL	0.5 GPM					
L-2	LAVATORY, COUNTER MTD, ADA	1/2"	1/2"	1 1/4"	1 1/4"	---	COUNTER MOUNTED, SEE ARCHITECTURAL	0.5 GPM					
MS-1	MOP SINK	1/2"	1/2"	3"	1 1/2"	---	FLOOR MOUNT	2.5 GPM					
S-1	COUNTER SINK, DOUBLE COMPARTMENT	1/2"	1/2"	1-1/2"	1-1/2"	---	COUNTER MOUNTED, SEE ARCHITECTURAL	1.5 GPM					
UR-1	URINAL	---	1"	2"	1-1/2"	---	WALL HUNG	1.0 GPF					
UR-2	URINAL, ADA	---	1"	2"	1-1/2"	---	WALL HUNG, ADA	1.0 GPF					
WC-1	WATER CLOSET, WALL HUNG, FLUSH VALVE	---	1-1/2"	4"	2"	---	WALL HUNG	1.1 GPF					
WC-2	WATER CLOSET, WALL HUNG, FLUSH VALVE, HDCP	---	1-1/2"	4"	2"	---	WALL HUNG, ADA	1.1 GPF					
WC-3	WATER CLOSET, FLOOR MTD., FLUSH VALVE, HDCP	---	1-1/2"	4"	2"	---	FLOOR MOUNT, ADA	1.1 GPF					
WH-1	WALL HYDRANT	---	3/4"	---	---	---	18" A.F.F.	2.5 GPM					

NOTES:
1. PROVIDE WITH CHROME PLATED P-TRAP AND SUPPLY PIPES WITH ANGLE STOPS.
2. PROVIDE WITH PVC P-TRAP AND SUPPLY PIPES WITH ANGLE STOPS.

PLUMBING PUMP SCHEDULE

MARK	WEIGHT	SERVES	TYPE	FLOW GPM	HEAD FT WG	ELECTRICAL DATA					MANUFACTURER AND MODEL NUMBER	REMARKS
						RPM	HP	VOLTS	PH	HZ		
DHWP-1		DHWR	INLINE								TACO	

NOTES:
1. PROVIDE UNIT WITH WATER-IMMERSION TEMPERATURE SENSOR AND TIMER. ON-OFF CONTROL WITH PROGRAMMABLE SEVEN-DAY CLOCK AND MANUAL OVERRIDE.
2. START AT 105 °F / STOP AT 120 °F.

GAS-FIRED WATER HEATER SCHEDULE

MARK	WEIGHT	DIMENSIONS DIA. X H	FUEL TYPE	INPUT RATING (MBH)	MINIMUM RECOVERY AT RISE SHOWN (GPH)	EWT (°F)	LWT (°F)	STORAGE CAPACITY (GALLONS)	MANUFACTURER AND MODEL NUMBER	REMARKS
GWH-1	1800	34 X 81	NAT. GAS	600	699	40	140	130	PVI CONQUEST 60 L 130A-GCML	1
GWH-2	1800	34 X 81	NAT. GAS	600	699	40	140	130	PVI CONQUEST 60 L 130A-GCML	1
GWH-3	1800	34 X 81	NAT. GAS	600	699	40	140	130	PVI CONQUEST 60 L 130A-GCML	1

NOTES:
1. PROVIDE WITH CONDENSATE NEUTRILIZATION KIT AND CONCENTRIC VENT.

SUMP PUMP SCHEDULE

MARK	LOCATION	FLOW GPM	HEAD FT WG	ELECTRICAL DATA					MANUFACTURER AND MODEL NUMBER	REMARKS
				RPM	HP	VOLTS	PH	HZ		
SP-1,2	SEE PLANS	50	20	3450	1			60	STANCOR AHS-10	1,2,3

NOTES:
1. INSTALL TO MEET STATE ELEVATOR CODE REQUIREMENTS.
2. PROVIDE UNIT WITH STANCOR OIL-MINDER CONTROLS WITH OM-300 FLOATS.
3. COORDINATE ELECTRICAL CORD LENGTH WITH ELECTRICAL CONTRACTOR.

DESIGNED: AJP ISSUE DATE: 11/26/2019
DRAWN: AJP/MLB REVISIONS:
CHECKED: Checker

No.:	DATE:	BY:	DESCRIPTION:

THIS DRAWING IS BEING MADE AVAILABLE BY SCHEMMER FOR USE ON THIS PROJECT IN ACCORDANCE WITH THE AGREEMENT BETWEEN SCHEMMER AND THE OWNER. SCHEMMER DOES NOT REPRESENT THIS DRAWING FOR ANY USE OF THIS DRAWING ON ANY OTHER PROJECT OR IN ACCORDANCE WITH THE AGREEMENT.

SCHEMMER
Design with Purpose. Build with Confidence.

TETRAD PROPERTY GROUP
GOLDENROD KEARNEY SENIOR LIVING
22ND AVENUE,
KEARNEY, NE 68845

SCHEDULES - PLUMBING

PROJECT NO.: 07435.002

P501