1 AREA A - ROOF PLAN
SCALE: 1/8" = 1'-0"

ROOF NOTES:

1. ROOF AREAS SHOWN AS HATCHED ON THE ROOF PLAN ARE AREA WERE THE ROOF DECK ARE TO BE INSTALLED LEVEL AND THE SLOPE TO THE ROOF DRAINS ARE TO BE ACCOMPLISHED BY THE USE TO TAPERED INSULATION.
2. ALL ROOFING IS A MEMBRANE ROOFING SYSTEM SEE THE PROJECT MANUAL. MEMBRANE ROOF FLASHING AS REQUIRED AT INTERFACE OF NEW ROOFING SYSTEM TO EXISTING.
3. ALL ROOF CRICKETS ARE TAPERED INSULATION WITH A 1/2" MIN. SLOPE PER FOOT.
4. ON THIS PLAN "RD" STANDS FOR ROOF DRAIN, "OD" STANDS FOR OVERFLOW DRAIN.
5. CONTRACTOR SHALL VERIFY ANY OTHER ROOF PENETRATIONS NOT SHOWN HERE WITH THE MECHANICAL AND ELECTRICAL PLANS.
6. CONTRACTOR SHALL EXTEND THE ROOF CRICKETS AS CLOSE AS POSSIBLE TO ALL SCUPPER LOCATIONS.
7. MECHANICAL CONTRACTOR SHALL VERIFY THE HEIGHTS OF CURBS AND LEGS TO BE PROVIDED FOR ROOF TOP UNITS DUE TO THE TAPERED INSULATION USED IS SOME AREAS OF THE ROOF.
8. INSULATION BASE LAYER SHALL BE R-20 MIN.
9. POSITIVE DRAINAGE SHALL BE PROVIDED IN ALL AREAS OF THE ROOF TO THE ROOF DRAINS.



KEY PLAN

TRUE NORTH

DESIGNED: Designer
DRAWN: Author
CHECKED: Checker

ISSUE DATE: 11/26/2019
REVISIONS:

No.:	DATE:	BY:	DESCRIPTION:

THIS DRAWING IS BEING MADE AVAILABLE BY SCHEMMER FOR USE BY THE OWNER IN ACCORDANCE WITH THE PROFESSIONAL SERVICES AGREEMENT FOR THE PROJECT. SCHEMMER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR ANY USE OF THIS DRAWING BY ANYONE OTHER THAN THE OWNER IN ACCORDANCE WITH THE PROFESSIONAL SERVICES AGREEMENT.

DD - NOT FOR CONSTRUCTION

SCHEMMER
Design with Purpose. Build with Confidence.

TETRAD PROPERTY GROUP
GOLDENROD KEARNEY SENIOR LIVING
22ND AVENUE,
KEARNEY, NE 68845

ROOF PLAN - AREA A

PROJECT NO.: 07435.002

A107

C:\Users\klleanor\Documents\Revit_temp\07435002_ARCH_R19_MAIN BUILDING_klleanor@schemmer.com.rvt
11/22/2019 3:50:15 PM

Project Number w/out "." for PDF numbering- 2-ROOF PLAN - AREA A