SYMBOL LEGEND

PLAN VIEW

SHEAR WALL
MASONRY-VENEER
MASONRY-CMU
STUD WALL

SECTION / ELEVATION VIEW

CONCRETE
FLEXIBLE INSULATION
GRAVEL
GROUT
EARTH / COMPACTED
PLYWOOD
EARTH / NONCOMPACTED
WOOD (FINISH)
RIGID INSULATION
MASONRY-CMU FACE
JOINT FILLER
MASONRY-CMU
STEEL
MASONRY-VENEER
GYPSUM

REFERENCE LEGEND

HEADER CALLOUT IN STUD WALL	H-X	HEADER DESIGNATION
LINTEL CALLOUT IN MASONRY WALL	L-X	LINTEL DESIGNATION
METAL STUD WALL CALLOUT	X	LETTER INDICATES METAL STUD WALL TYPE
CIP WALL CALLOUT	X	LETTER INDICATES CIP WALL TYPE
PRECAST CONC WALL CALLOUT	X	LETTER INDICATES PRECAST CONC WALL TYPE
CMU WALL CALLOUT	X	LETTER INDICATES CMU WALL TYPE
SHEAR WALL CALLOUT	SHEAR WALL TYPE 'X' MIN L = X'-X"	SHEAR WALL TYPE DESIGNATION SHEAR WALL LENGTH
WALL FOOTING CALLOUTS	GBX-X CFX-X TSX-X	GRADE BEAM DESIGNATION CONTINUOUS FOOTING DESIGNATION THICKENED SLAB DESIGNATION
PAD FOOTING CALLOUTS	FX-X	REFERENCE DESIGNATION
PILE CAP CALLOUT	0001 [T.O.P. = 100'-0"] [T.O.P. = X000.00']	REFERENCE DESIGNATION ARCH ELEVATION CIVIL ELVATION
REFERENCE NOTE	X	REFERENCE DESIGNATION
ROOM / FRAMING ELEVATION	1 1 XX-XX 1 1	ELEVATION LETTER DIRECTION OF VIEW SHEET NUMBER
EXTERIOR ELEVATION	1 1 XX-XX 1 1	DIRECTION OF VIEW ELEVATION LETTER SHEET NUMBER
PLAN DETAIL	X XX-XX	DETAIL NUMBER SHEET NUMBER
SECTION/ DETAIL	SIM X XX-XX	SECTION/DETAIL NUMBER SHEET NUMBER INDICATES DIRECTION OF VIEW
NEW COLUMN	X	LETTER INDICATES NEW COLUMN LINE
EXISTING COLUMN	X	LETTER INDICATES EXISTING COLUMN LINE
MATCHLINE	AREA A AREA B	
LEVEL	NAME ELEVATION	LEVEL CALLOUT DESIGNATION ELEVATION DESIGNATION
TITLE MARKER	1 VIEW NAME SCALE: 1/8" = 1'-0"	GRAPHIC AREA FOR DRAWING DETAIL NUMBER TITLE SCALE OF THE DRAWING
NORTH ARROW	NORTH PLAN NORTH TRUE NORTH	

ABBREVIATIONS

AB	ANCHOR BOLT
ACI	AMERICAN CONCRETE INSTITUTE
AFF	ABOVE FINISH FLOOR
AGG	AGGREGATE
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
AL	ALUMINUM
ANCH	ANCHOR
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
APPD	APPROVED
APPROX	APPROXIMATE
ARCH	ARCHITECTURAL OR ARCHITECT
AUTO	AUTOMATIC
AVG	AVERAGE
L	ANGLE
BL	BUILDING LINE
BLDG	BUILDING
BLKG	BLOCKING
BO	BOTTOM OF
BOT	BOTTOM
BRCG	BRACING
BRDG	BRIDGING
BRG	BEARING
BS	BOTH SIDES
BW	BOTH WAYS
C	CHANNEL (STRUCTURAL SHEETS)
CF	CUBIC FEET
CIP	CAST IN PLACE
CJ	CONTROL JOINT
CL	CENTER LINE
CLR	CLEAR
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
COMP	COMPRESSIBLE
CONC	CONCRETE
CONN	CONNECTION
CONSTR JT	CONSTRUCTION JOINT
CONT	CONTINUOUS (CONTINUATION)
CU YD	CUBIC YARDS
D	DEPTH (DEEP)
d	PENNY (as in nail - 10d)
DBL	DOUBLE
DEMO	DEMOLITION
DIA	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DL	DEAD LOAD
DWG	DRAWING
DWLS	DOWELS
EF	EACH FACE
EJ	EXPANSION JOINT
EL	ELEVATION - GRADE OR BUILDING
ELEV	ELEVATOR
EQ	EQUAL
EQUIP	EQUIPMENT
EW	EACH WAY
EXIST	EXISTING
EXPN	EXPANSION
EXT	EXTERIOR
F	FAHRENHEIT
FD	FLOOR DRAIN
FDN	FOUNDATION
FIN	FINISH
FLR	FLOOR
FT	FEET (FOOT)
FTG	FOOTING
FV	FIELD VERIFY
GA	GAGE OR GAUGE
GALV	GALVANIZED
GRTG	GRATING
GWB	GYPSUM WALLBOARD
H or HT	HEIGHT (HIGH)
HDR	HEADER
HK	HOOK
HORIZ	HORIZONTAL(LY)
HPT	HIGH POINT
HS	HIGH STRENGTH
ID	INSIDE DIAMETER
IN	INCH
INSUL	INSULATION
INT	INTERIOR
KIP or K	KILOPOUND (1000 LBS)
KP	KICK PLATE
L	LENGTH (LONG)
LBS	POUNDS
LDG	LOADING
LL	LIVE LOAD
LLBB	LONG LEG BACK TO BACK
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LNTL	LINTEL
LONG	LONG LONGITUDINAL
LP	LOW POINT
LT WT	LIGHT WEIGHT
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MC	MISCELLANEOUS CHANNELS
MECH	MECHANICAL
MET	METAL
MFG	MANUFACTURING
MFR	MANUFACTURER
MIN	MINIMUM
MISC	MISCELLANEOUS
NIC	NOT IN CONTRACT
NO	NUMBER
NR	NOT REQUIRED
NTS	NOT TO SCALE
OC	ON CENTER(S)
OCEW	ON CENTER EACH WAY
OD	OUTSIDE DIAMETER
OH	OVERHEAD
OPNG	OPENING
OPP	OPPOSITE
OZ	OUNCE
PC	PRECAST
PERF	PERFORATED
PLWD	PLYWOOD
POL	POLISH(ED)
PREFAB	PREFABRICATED
PS	PRESSED STEEL
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
QTY	QUANTITY
R	RADIUS
RD	ROOF DRAIN
REF	REFERENCE
REINF	REINFORCEMENT
REQD	REQUIRED
RTU	ROOF TOP UNIT
SCHED	SCHEDULE
SDI	STEEL DECK INSTITUTE
SF	SQUARE FOOT (FEET)
SHTG	SHEATHING
SIM	SIMILAR
SJI	STEEL JOIST INSTITUTE
SL	SNOW LOAD
SLBB	SHORT LEG BACK TO BACK
SPEC	SPECIFICATIONS
SS	STAINLESS STEEL
STD	STANDARD
STGR	STRINGER
STIFF	STIFFENER
STIRR	STIRRUPS
STL	STEEL
STR	STRUCTURAL
SUSP	SUSPENDED
TEMP	TEMPERATURE
TO	TOP OF
TOB	TOP OF BEAM
TOC	TOP OF CONCRETE
TOF	TOP OF FOOTING
TOS	TOP OF STEEL
TOW	TOP OF WALL
TRANS	TRANSVERSE
TYP	TYPICAL
UNEX	UNEXCAVATED
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
VEST	VESTIBULE
W	WIDE (WIDTH)
W/	WITH
W/O	WITHOUT
WF	WIDE FLANGE
WL	WIND LOAD
WP	WORK POINT
WT	WEIGHT
WWF	WELDED WIRE FABRIC

SCHEDULES

CONT. FOOTING SCHEDULE

MARK	WIDTH	DEPTH	REINFORCING

GRADE BEAM SCHEDULE

MARK	WIDTH	DEPTH	LONGITUDINAL REINFORCING	STIRRUPS
GB1-6	1' - 6"	3' - 4"	(3) #5 BARS BOT., (3) #5 BARS TOP	#4 @ 24" O.C.

PAD FOOTING SCHEDULE

MARK	PLAN SIZE	DEPTH	REINFORCING
F3.0A	3'-0" X 3'-0"	1' - 0"	(4) #5 BARS EACH WAY, BOTTOM
F3.0B	3'-0" X 3'-0"	3' - 4"	(3) #6 BARS EACH WAY, TOP & BOTTOM
F3.5B	3'-6" X 3'-6"	3' - 4"	(4) #6 BARS EACH WAY, TOP & BOTTOM
F4.0 A	4'-0" X 4'-0"	1' - 0"	(5) #5 BARS EACH WAY, BOTTOM
F4.0 B	4'-0" X 4'-0"	3' - 4"	(5) #5 BARS EACH WAY, BOTTOM

THICKENED SLAB SCHEDULE

MARK	WIDTH	DEPTH	REINFORCING
TS1-6	1' - 6"	1' - 0"	(3) #5 BARS LONG. BOT
TS2-0	2' - 0"	1' - 0"	(3) #5 BARS LONG. BOT

MASONRY WALL REINF. SCHEDULE

MARK	WIDTH	REINFORCING	
		VERTICAL	HORIZONTAL
	0' - 6"	#5 @ 32" O.C. MAX.	LADDER TYPE - 2 - W1.7 WIRES @ 16" O.C.
A	0' - 8"	#5 @ 32" O.C. MAX.	LADDER TYPE - 2 - W1.7 WIRES @ 16" O.C.

MASONRY LINTEL SCHEDULE

MARK	BEARING	REINFORCING
L-1	8"	16" BOND BEAM W/ (2) #5 CONT. @ BOT.

SINGLE ANGLE LINTEL SCHEDULE

LINTEL CLEAR SPAN	LINTEL SIZE	LINTEL MINIMUM END BEARING
3	L4X4X1/4	4"
4	L4X4X1/4	4"
5	L4X4X5/16	4"
6	L4X4X3/8	8"
7	L4X4X3/8	8"
8	L6X4X3/8	8"

WOOD STUD WALL SCHEDULE

LOCATION	STUD SIZE	STUD SPAC. (IN. O.C.)	SPECIES & GRADE
TYPICAL NON-LOAD-BEARING PARTITION WALL	2X4	16	SPF NO. 1/NO. 2
INTERIOR SHEAR WALLS PARALLEL TO ROOF TRUSSES	2X6	16	SPF NO. 1/NO. 2
FLOOR 2, EXTERIOR LOAD BEARING WALLS	2X6	16	SPF NO. 1/NO. 2
FLOOR 2, INTERIOR LOAD BEARING WALLS	2X6	16	SPF NO. 1/NO. 2
FLOOR 1, EXTERIOR LOAD BEARING WALLS	2X6	16	SPF NO. 1/NO. 2
FLOOR 1, INTERIOR LOAD BEARING WALLS	2X6	16	SPF NO. 1/NO. 2

WOOD HEADER SCHEDULE

MARK	SIZE	# OF JACK STUDS	# OF KING STUDS	VENEER SUPPORT ANGLE
H-X	5 1/8"X12" GLB	2	3	N.A.

SHEAR WALL SCHEDULE

MARK	SHEATHING	EDGE ATTACH	FIELD ATTACH	HOLDDOWN ANCHOR	NOTES

REF. NOTES (x)

PROJECT STRUCTURAL REFERENCED NOTES

1 MANUFACTURED WOOD TRUSSES @ 24" O.C.

STRUCTURAL SHEET LIST

S 00	STRUCTURAL INFO SHEET
S 01	STRUCTURAL NOTES
S101	FOUNDATION PLAN - AREA A
S102	FOUNDATION PLAN - AREA B & C
S103	SECOND FLOOR FRAMING PLAN - AREA A
S104	SECOND FLOOR FRAMING PLAN - AREA B & C
S105	THIRD FLOOR FRAMING PLAN - AREA A
S106	THIRD FLOOR FRAMING PLAN - AREA B & C
S107	ROOF FRAMING PLAN - AREA A
S108	ROOF FRAMING PLAN - AREA B & C
S201	TYPICAL FOUNDATION DETAILS
S202	FOUNDATION DETAILS
S301	TYPICAL FRAMING DETAILS
S302	TYPICAL FRAMING DETAILS
S303	FRAMING DETAILS

ISSUE DATE: 11/5/2019
REVISIONS:
No.: DATE: BY: DESCRIPTION:

DESIGNED: MJN
DRAWN: MJN
CHECKED: KMW

THIS DRAWING IS BEING MADE AVAILABLE BY SCHEMMER FOR USE BY THE OWNER IN ACCORDANCE WITH THE AGREEMENT FOR ARCHITECTURAL SERVICES BETWEEN SCHEMMER AND THE OWNER. SCHEMMER IS NOT RESPONSIBLE FOR ANY USE OF THIS DRAWING BY THE OWNER OR OTHERS EXCEPT IN ACCORDANCE WITH THE AGREEMENT.

DD - NOT FOR CONSTRUCTION

SCHEMMER
Design with Purpose. Build with Confidence.

TETRAD PROPERTY GROUP
GOLDENROD KEARNEY SENIOR LIVING
ADDRESS (OPEN PROJECT INFO TO ENTER)
ADDRESS

STRUCTURAL INFO SHEET

PROJECT NO.: 07435.002

S 00

C:\Users\nschmidt\Documents\Revit_temp\07435002-STRUCT_R19_nschmidt.rvt
11/22/2019 11:42:32 AM

Project Number w/out "." for PDF numbering- 3-STRUCTURAL INFO SHEET