

3 SOUTH ELEVATION - AREA C
SCALE: 1/8" = 1'-0"

ROOF/CLG/FLR ASSEMBLIES

TYPE R1	1-HOUR RATING UL-P533: ASPHALT SHINGLES, 30# ROOFING FELT, ROOF SHEATHING, PITCHED CHORD WOOD ROOF TRUSSES (SEE STRUCTURAL), BATT INSULATION (R-38 MIN.) 7/8" HAT CHANNEL @ 12" OC, 6 MIL POLY VAPOR BARRIER, 5/8" TYPE 'C' GWB.
TYPE R2	1-HOUR RATING UL-P533: MEMBRANE ROOF, MIN. 2" POLY-ISO BOARD INSULATION (SEE SPEC), WOOD ROOF SHEATHING, PARALLEL CHORD WOOD ROOF TRUSSES (SEE STRUCTURAL), BATT INSULATION (R-38 MIN) 7/8" HAT CHANNEL @ 12" OC, VAPOR BARRIER, 6 MIL POLY VAPOR BARRIER, 5/8" TYPE 'C' GWB.
TYPE F1	1-HOUR RATING UL L550: MINIMUM 3/4" GYPSUM FLOOR TOPPING, MINIMUM 1/4" SOUND MATT, 3/4" T&G PLYWOOD SUBFLOOR, PARALLEL CHORD TRUSSES (SEE STRUCTURAL), BATT INSULATION, 1/2", 25 GA RESILIENT CHANNELS @ 12" OC, 5/8" TYPE 'C' GWB.
TYPE F2	1-HOUR RATING UL L569: MINIMUM 3/4" GYPSUM FLOOR TOPPING, MINIMUM 1/4" SOUND MATT, 3/4" T&G PLYWOOD SUBFLOOR, 2X10 JOISTS (SEE STRUCTURAL), FILL CAVITY W/ BATT INSULATION, 1/2", 25 GA RESILIENT CHANNELS @ 12" OC, 5/8" TYPE 'C' GWB.

4 NORTH ELEVATION - AREA C
SCALE: 1/8" = 1'-0"



1 EAST ELEVATION - AREA B
SCALE: 1/8" = 1'-0"



2 EAST ELEVATION - AREA C
SCALE: 1/8" = 1'-0"

DESIGNED: Designer
DRAWN: Author
CHECKED: Checker

ISSUE DATE: 11/26/2019
REVISIONS:

No.:	DATE:	BY:	DESCRIPTION:

THIS DRAWING IS BEING MADE AVAILABLE BY SCHEMMER FOR USE BY THE OWNER IN ACCORDANCE WITH THE SCHEMMER AGREEMENT WITH THE OWNER. SCHEMMER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR ANY USE OF THIS DRAWING BY ANY OTHER PERSON OR ENTITY IN ACCORDANCE WITH THE SCHEMMER AGREEMENT.

DD - NOT FOR CONSTRUCTION

SCHEMMER
Design with Purpose. Build with Confidence.

TETRAD PROPERTY GROUP
GOLDENROD KEARNEY SENIOR LIVING
22ND AVENUE,
KEARNEY, NE 68845

EXTERIOR BUILDING ELEVATIONS

PROJECT NO.: 07435.002

A203

C:\Users\kfleenor\Documents\Revit_temp\07435002_ARCH_R19_MAIN BUILDING_kfleenor@schemmer.com.rvt
11/22/2019 4:03:30 PM
Project Number w/out "." for PDF numbering- 2-EXTERIOR BUILDING ELEVATIONS