

1 SECTION @ MAIN ENTRY
SCALE: 1/8" = 1'-0"



4 TYPICAL SECTION @ AREA A
SCALE: 1/8" = 1'-0"

ROOF/CLG/FLR ASSEMBLIES

TYPE R1	1-HOUR RATING UL-P533: ASPHALT SHINGLES, 30# ROOFING FELT, ROOF SHEATHING, PITCHED CHORD WOOD ROOF TRUSSES (SEE STRUCTURAL), BATT INSULATION (R-38 MIN.) 7/8" HAT CHANNEL @ 12" OC, 6 MIL POLY VAPOR BARRIER, 5/8" TYPE 'C' GWB.
TYPE R2	1-HOUR RATING UL-P533: MEMBRANE ROOF, MIN. 2" POLY-ISO BOARD INSULATION (SEE SPEC), WOOD ROOF SHEATHING, PARALLEL CHORD WOOD ROOF TRUSSES (SEE STRUCTURAL), BATT INSULATION (R-38 MIN) 7/8" HAT CHANNEL @ 12" OC, VAPOR BARRIER, 6 MIL POLY VAPOR BARRIER, 5/8" TYPE 'C' GWB.
TYPE F1	1-HOUR RATING UL L550: MINIMUM 3/4" GYPSUM FLOOR TOPPING, MINIMUM 1/4" SOUND MATT, 3/4" T&G PLYWOOD SUBFLOOR, PARALLEL CHORD TRUSSES (SEE STRUCTURAL), BATT INSULATION, 1/2", 25 GA RESILIENT CHANNELS @ 12" OC, 5/8" TYPE 'C' GWB.
TYPE F2	1-HOUR RATING UL L569: MINIMUM 3/4" GYPSUM FLOOR TOPPING, MINIMUM 1/4" SOUND MATT, 3/4" T&G PLYWOOD SUBFLOOR, 2X10 JOISTS (SEE STRUCTURAL), FILL CAVITY W/ BATT INSULATION, 1/2", 25 GA RESILIENT CHANNELS @ 12" OC, 5/8" TYPE 'C' GWB.



2 TYPICAL SECTION @ LIVING UNITS
SCALE: 1/8" = 1'-0"

DESIGNED: Designer
DRAWN: Author
CHECKED: Checker

ISSUE DATE: 11/26/2019
REVISIONS:

No.:	DATE:	BY:	DESCRIPTION:

THIS DRAWING IS BEING MADE AVAILABLE BY SCHEMMER FOR USE AS INSTRUMENT OF SERVICE ONLY IN ACCORDANCE WITH THE AGREEMENT FOR PROFESSIONAL SERVICES BETWEEN SCHEMMER AND THE OWNER. ANY OTHER USE OR REUSE IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF SCHEMMER.

DD - NOT FOR CONSTRUCTION

SCHEMMER
Design with Purpose. Build with Confidence.

TETRAD PROPERTY GROUP
GOLDENROD KEARNEY SENIOR LIVING
22ND AVENUE,
KEARNEY, NE 68845

BUILDING SECTIONS

PROJECT NO.: 07435.002

A204

C:\Users\kfleenor\Documents\Revit_temp\07435002_ARCH_R19_MAIN BUILDING_kfleenor@schemmer.com.rvt
11/22/2019 4:18:25 PM

Project Number w/out "." for PDF numbering: 2-BUILDING SECTIONS